

Trailer Checklist

Use this for a quick check that the trailer is set up and taken down appropriately!



Think Make Create

LABS

© 2018 Minnesota Online and Center Foundation | Project Charter 6/18

Unhitching/Parking the Trailer:

- ✓ Ensure wheel chocks secured on either side of tire
- ✓ Lower jack until it just touches the ground
- ✓ Remove coupler pin and open coupler lock
- ✓ Remove chains, electrical and brake wire
- ✓ Raise jack until receiver is above the ball height on tow vehicle
- ✓ Slowly drive tow vehicle away
- ✓ Lower jack until trailer is level
- ✓ Place coupler lock on trailer receiver
- ✓ Drop rear stabilizers - *Push in, then down on bars, drop foot*
- ✓ Ensure wheel chocks secured on either side of tire
- ✓ Open and secure doors

Before Hauling:

- ✓ Use the correct ball size—always!
- ✓ Chains (crossed, not dragging, not too tight for turns), electrical/brakes, and emergency brake wire are all secure
- ✓ All brake lights and blinkers are working
- ✓ Secure coupler lock correctly and ensure coupler pin is in place

Hitching/Hauling the Trailer:

- ✓ Ensure wheel chocks secured on either side of tire
- ✓ Lift rear stabilizers - *Lift foot, push down, then in on bars*
- ✓ Secure all doors, remove coupler lock
- ✓ Lift jack so receiver is above the ball height on tow vehicle
- ✓ Back up tow vehicle to position - *where receiver can be lowered onto ball*
- ✓ Lower jack until receiver is secure on ball
- ✓ Close coupler lock and secure coupler pin
- ✓ Secure chains, electrical and brake wire
- ✓ Remove wheel chocks